



COOLOOLABIN DAM



Client Doval Constructions **Duration** Nov 2015 to Dec 2015

Location Sunshine Coast, QLD **Value** \$280K

Details Doval engaged Decotec to remove 200 tonne of concrete from the Cooloolabin Dam spillway crest to reduce the dam capacity due to modern safety constraints. The spillway was cut into 27 sections using diamond wire and then hydraulically split into a total of 80 sections, which were lifted out with a barge crane.



"Decotec offered good solutions to problems, were co-operative in all dealings and a pleasure to work with..." Kevin Mattushek | Doval Contracts Manager