


FAIRBAIRN DAM

DECOTEC



DATE	LOCATION	CLIENT	VALUE
Oct 2019 - Jun 2020	Emerald, QLD	SRG Global Civil	\$860K

SRG were engaged by SunWater to install 78 post-tensioned anchors into the spillway crest to strengthen the dam. SRG required Decotec to core drill a $\varnothing 1000\text{mm} \times 1.5\text{m}$ deep hole followed by a $\varnothing 250\text{mm} \times 3.5\text{m}$ deep hole for each anchor. ITP's were utilised to record all details to ensure holes were cored well within the required tolerances.

"Superior quality and ability to adapt to the contractors needs. Field workers showed great potential."

Manuel Barbara | SRG Senior Project Engineer